

Useful guide when the final contract differs from the original quote. If you have decided not to select certain options offered by your supplier, these may now be your responsibility.

Table of typical options sometimes rejected at purchase

When

As soon as possible after signing the contact

TYPICAL OPTIONS SOMETIMES REJECTED BY BUYERS	NOW UNDER YOUR RESPONSIBILITY	ELEMENTS TO CONSIDER	DONE
Lifting equipment for installation	Equipment rental and their management	The buyer must provide the equipment models requested by the overhead crane manufacturer (see the list of equipment required for installation).	
Transportation of the overhead crane to the installation site	Full transportation management	Follow the overhead crane manufacturer's guidelines carefully.	
Weights for the load test	Provide weights available on site or rent them	Weights and slings must be suitable and allow weights to be lifted and moved at 100% and 125% of the rated capacity.	
End stops	Ensure that the end stops are in place by the day of installation	Usually provided by the structural contractor: make sure that they comply with the overhead crane manufacturer's specifications.	
Verification of the concrete floor (when a structure is included in the project)	Validate: concrete thickness (cracks within tolerances), column positioning (relative to obstacles), saw-cut joint, and slab edge	Closely follow the overhead crane supplier's guidelines during verifications.	

New building

Goal: reduce unforeseen events that would delay the commissioning date